

Before the  
**Arizona Corporation Commission**

**Arizona Public Service Company  
2009 Summer Assessment**

March 24, 2009



# Presenters

**Bob Smith**

Director, Asset Management and Planning

**Tom Carlson**

Director, Fuels

**Tom Glock**

Director, Power Operations



# Agenda

- System Improvements
- Planned Maintenance Activities
- Emergency Preparedness
- Fuel and Purchase Power
- Loads and Resources
- Transmission System Adequacy
- Contingency Planning
- Conclusions



# System Improvements Emergency Planning

Bob Smith  
Director

Asset Management and Planning



# APS Service Statistics

- 11 counties
- 34,645 sq. mi. CC&N area
- 1.1 million customers
- 411 substations
- 28,022 distribution line miles
- 5,234 transmission line miles
- 54 generation units



# Reliability Supply Chain



Service



Step-down  
Transformer



Substation



Transmission Lines  
69 kV



# Delivery System Construction


	<u>2008</u>	<u>2009</u>
Distribution Sub MVA	717	119
Trans. Sub MVA	508	854
Trans. Line Miles, New	17	52
Trans. Lines Miles, Rebuild	10	42

Total distribution system substation capacity = 13,000 MVA

Total transmission system substation capacity = 25,000 MVA



# State Area Transmission



Red = 500 kV

Green = 345 kV


Blue = 230 kV

Black = 115 kV






# Four Corners/Cholla System Transmission



- Four Corners and Cholla Power Plants
- Four Corners-Moenkopi-Eldorado 500kV line
- Four Corners-Cholla 345kV lines
- Cholla-Pinnacle Peak 345kV lines
- Cholla-Saguaro 500kV line




# Navajo System Transmission



- Navajo Power Plant
- Navajo-Crystal 500kV line
- Navajo-Westwing 500kV lines



# Palo Verde Hub Transmission



- Palo Verde Nuclear Plant and Hassayampa Gas Power Plants
- Palo Verde West
  - PV-Devers 500kV line
  - Hassayampa-North Gila 500kV line
- Palo Verde East
  - PV-Westwing 500kV lines
  - PV-Rudd 500kV line
  - Hassayampa-Jojoba-Kyrene 500kV line




# Mead-Phoenix Transmission



- Mead-Phoenix 500kV line



# Transmission Substation Additions 2009



Sugarloaf 500/69kV Substation

Dugas 500/69kV Substation


Milligan 230/69kV Substation



# Planned Reliability Activities



# Planned Generation Maintenance Pre-Summer 2009



# Transmission and Distribution Maintenance and Monitoring

- Transformer and circuit breaker bushing replacement program
- Maintenance Optimization Project
- On-line equipment monitoring
- TOAN analysis software
- Annual line inspections





# Vegetation Management

- Focusing on providing safe, reliable power and reducing wildfire risk
- Wildfire planning
  - Wildfire Academy, Prescott
  - Forest Service relationships / conditions monitoring
  - On-Site Incident Command presence
- Transmission corridor clearing
  - 2008 – completed 441 miles 115 kV and above
  - 2009 – EHV lines scheduled for completion
- Sub-transmission, distribution on track
- GIS\Lidar project

# Lidar Equipped Helicopter



# Emergency Equipment

- Mobile 69/12kV Transformers
- Emergency Towers - two Lindsey towers
- Generator – 1,500 KW Mobile Unit
- Mobile Command Center



# Mobile Transformer



# Lindsey Towers



# Mobile Generator



# Mobile Command Center



# Preparing for Emergencies Governmental Engagement

- Coyote Crisis – March 2009 State drill
- Continuing NIMS certification
- Incident Command Training / First Responders
- Joint training, planning, drills
- Agency familiarization – facility layout
- General business planning
  - Curtailment Plan annual filing
  - ECC Disaster Recovery Exercise, March 2009
  - Disaster Recovery / Business Resumption Plans





# Summary

- Infrastructure will be in place to meet summer 2009 needs
- Maintenance efforts on track
- Coordination, integration with emergency planners in place
- Internal emergency preparedness
  - Plans
  - Training
  - Equipment


# APS Fuels Procurement

Tom Carlson  
Director, Fuels




# APS Generation


- Base Load, Nuclear
  - Palo Verde 
- Base Load, Coal
  - Four Corners 
  - Cholla 
  - Navajo 
- Intermediate and Peak Load, Gas, Oil back-up
  - Phoenix Area
    - West Phoenix
    - Sundance
    - Redhawk
    - Ocotillo
  - Saguaro 
  - Yucca 
  - Douglas 



# Meeting Customers' Needs



# 2009 Projected Energy Mix



# Nuclear: Palo Verde

- Fuel sourced from multiple suppliers
- 100% of 2009 requirements under firm contract



# Coal: Four Corners Power Plant

- Mine mouth plant with full supply contract with BHP Navajo Mine
- Contract term currently runs through 2015
- Coal supplier maintains in-pit and processing plant inventory
- 60 days inventory available




# Coal: Cholla Power Plant

- Current inventory and contract commitments provide adequate coal for the projected 2009 burn
- Primary supply source is delivered by rail from the El Segundo Mine near Grants, NM
- Expected inventory 45-60 days





# Natural Gas Pipelines Serving Arizona



# Natural Gas: Transportation

- APS has sufficient firm transport arranged with multiple suppliers to ensure reliable supply of natural gas to fully meet system needs.
- Transwestern Pipeline has begun delivery to Redhawk and Sundance power plants.
- El Paso Natural Gas supplies all APS natural gas plants.
- North Baja Pipeline continues to be delayed due to permitting issues.



# Natural Gas: Supply

- Gas Supply
  - Physical gas supply under firm contracts with reliable counterparties.
  - Gas purchased on daily spot market as needed to adjust for fluctuations.
  - Adequate supplies available from Permian/San Juan basins.
- Additional purchased power available to ensure reliability.



# Natural Gas: Storage

- Arizona Gas Storage Project
  - Open Season completed
  - APS submitted bid for capacity
  - Project discontinued due to insufficient customer interest
- Eloy Gas Storage Project
  - Initial capacity interest submitted by APS
  - Precedent agreements discussions on-going
  - Interconnects with El Paso and Transwestern
  - Project uncertainty related to brine disposal and customer interest
  - Estimated start-up in 2013




# Renewable Resources

1. Aragonne Mesa, 90 MW (Wind)
2. Salton Sea, 10 MW (Geothermal)
3. Prescott Airport, 2.9 MW (Solar)
4. STAR Center, 1.8 MW (Solar)



# Renewables – Annual Production

Central Station Annual Renewables Production



# Distributed Energy Systems

- 2002 – 2008: 2,412 installations (~ 8.5 MW/dc)
- 2008 Installations
  - \$9.1 million incentive payments
  - \$12.2 million commitments
  - Primarily “rooftop” photovoltaic and solar water heating, 60% increase over 2007
- Expect continued increase in participation in 2009



# Loads and Resources 2009

Tom Glock  
Director, Power Operations





# APS Owned Generation

<u>Fuel Source</u>	<u>Capacity - MW</u>
Nuclear	1,146
Coal	1,750
Gas Combined Cycle	1,900
Gas/Oil CT, Steam	1,467
Solar	3
Total	<hr/> 6,266



# Renewable Resources

<u>Resource</u>	<u>Planning Peak Contribution</u>	<u>Nameplate Capacity</u>
Aragonne Mesa Wind	16.1	90.0
Salton Sea CE Turbo	10.0	10.0
SWMP Biomass	14.5	14.5
Solar Generation	3.4	5.7
Total (MW)	<u>44.0</u>	<u>120.2</u>




# Generation Resources

	<u>Capacity (MW)</u>
Existing Generation	6,266
Long-term Contracts	
PacifiCorp Exchange	480
SRP (Contingent & Territorial)	238
Reliability RFP Purchases	1,150
Market Contract	90
Renewables	<u>44</u>
Subtotal	2,002
Short-term Market Contracts	<u>192</u>
Total Resources	8,460



# APS System Peak Loads




\* 2007 excludes UNSE at 401 MW Actual and 421 MW Forecast



# 2009 Peak Generation Resources and Load


Planned Reserve Margin to manage uncertainties:

1. Load forecast uncertainties
  - a. Extreme Weather
  - b. Economic Changes
2. Multiple generator outages
3. Transmission outages



# APS/SRP Maximum Load Serving Capability, Phoenix Valley


MW



Capability Load




# Yuma Area Peak Loads



# Yuma Area Maximum Load Serving Capability

MW





# Contingency Planning

# Training and Drills

- Backup Center Testing April - May
- Regional Black Start Drill March
- Exercise Load Curtailment Tools March - May
- Summer Studies (including fire corridors) May
- Transmission Path Operations May
- Emergency Operations Training May



# State Wide Operations Coordination

- Procedure developed by APS/SRP/WAPA/TEP
- Starting May 15<sup>th</sup>, each Monday, more as needed
- Wild fire Command Center participation
- APS/SRP/WAPA/TEP Coordinated Operations Conference Call



# State Wide Coordination

## APS/SRP/WAPA/TEP Logistics Schedule

- 7 AM Internal update on status of equipment and field conditions for each utility
- 9 AM Conference call topics:
  - Planned/current generation outages
  - Planned/current transmission outages
  - Weather forecast
  - Load forecast
  - Forest fires
- 10 AM Internal meeting to determine action plan based upon current events



# Conclusions



# APS is Well Prepared

- **Generation** resources are in place to meet customer load and reserve requirements
- **Transmission** capacity in place to import remote generation and purchases
- **Distribution** infrastructure improvements on schedule to meet customer needs
- **Plans in-place** to respond to extreme conditions

